MYSORE DIVISION.

Dated 25th May 1911.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 15th June 1911, for constructing a Munsiff's Court at Nanjangud. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1911.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government promissory notes, as earnest money, and be superscribed "Tender for constructing Munsiff's Court" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Serial No.	*Items of work*	*Per*	*Quantity.*
1.	Earthwork excavation and filling basement and consolidation ...	C. yd.	218
2.	Burnt brick in chunam	C. ft.	1,7125
3.	Do arch-work	„	609
4.	Burnt stone slab, 6″ thick	S. ft.	1,113
5.	Do beams roughly dressed	C. ft.	126
6.	Coping, complete	R. ft.	37
7.	Ornamental heads of buttresses	Each	14
8.	Plastering with chunam	Sqr.	152·50
9.	Whitewashing, 2 coats	„	91·13
10.	Colorwashing, 2 coats	„	61·37
11.	Teakwood work	C. ft.	425·59
12.	Teakwood door ⅓rd pannelled and ⅔rds venitioned	S. ft.	77
13.	Do battened	„	239
14.	Windows with pannel shutters and glazed one and iron bars ...	„	188
15.	Teakwood glazed semicirculars over doors and windows ...	„	100
16.	Strong battened door	„	27
17.	Ventilators with battened shutters and iron bars	„	12
18.	Wood oiling	Sqr.	31·96
19.	Chocolate painting	„	11·85
20.	Roofing with 1st class Mangalore tiles and teak reapers ...	„	13·06
21.	Ridge tiles set in mortar	R. ft.	25
22.	Pucka terracing	S. ft.	24·53
23.	Cornice with dentals (2¼′)	R. ft.	298
24.	Do (2¾′)	„	126
25.	Moulding (¼′×½′)	R. ft.	223
26.	Mangalore tiles flooring of 9″ square over 3″ concrete and cement pointing.	Sqr.	15·30
27.	Concrete flooring to roof and smoothening	C. ft.	146
28.	Zinc pipe to draw of water	L. S.	
29.	Erecting dias as per detailed estimate	„	
30.	Removing record racks and refixing.	„	
31.	Flooring with Caddappa slab over 3″ concrete and cement pointing	Sqr.	12·49
32.	Teakwood finials	Each	2
33.	Plain cornice	R. ft.	100
34.	Teakwood gate, complete	S. ft.	30
35.	Levelling and forming ground and gravelling the verandah compound and clearing site	L. S.	
36.	Wire fencing	„	

R. V. SUNDARAM IYER,
Executive Engineer.